

土工数量計算書

令和7年度 穴喰地区地域防災公園 造成工事

| 測 点 | 点間距離 | 土砂 | | | 軟岩 | | | 軟岩 (押土) | | | 備 考 |
|--------------|--------|------|-------|---------|----------------|--------|----------|----------------|--------|---------|----------------|
| | | 断 面 | 平 均 | 数 量 | 断 面 | 平 均 | 数 量 | 断 面 | 平 均 | 数 量 | |
| NO.1 +16.30 | | 0.0 | | | | | | | | | EL=53m |
| NO.2 | 3.67 | 25.1 | 12.55 | 46.1 | 0.0 | | | | | | EL=53m |
| NO.2 +10.00 | 10.00 | 14.7 | 19.90 | 199.0 | 62.0 | 31.00 | 310.0 | | | | EL=53m |
| NO.3 | 10.00 | 18.1 | 16.40 | 164.0 | 84.3 | 73.15 | 731.5 | | | | EL=53m |
| NO.3 +10.00 | 10.00 | 34.0 | 26.05 | 260.5 | 96.3 | 90.30 | 903.0 | | | | EL=53m |
| NO.4 | 10.00 | 7.6 | 20.80 | 208.0 | 178.8 | 137.55 | 1,375.5 | | | | EL=53m |
| NO.4 + 10.00 | 10.00 | 26.7 | 17.15 | 171.5 | 171.1 | 174.95 | 1,749.5 | | | | EL=53m |
| NO.5 | 10.00 | 18.8 | 22.75 | 227.5 | 180.0 | 175.55 | 1,755.5 | | | | EL=53m |
| NO.5 + 10.00 | 10.00 | 0.0 | 9.40 | 94.0 | 114.6 | 147.30 | 1,473.0 | | | | EL=53m |
| NO.6 | 10.00 | 0.0 | | | 83.7 | 99.15 | 991.5 | | | | EL=53m |
| NO.6 + 10.00 | 10.00 | 9.5 | 4.75 | 47.5 | 66.4 | 75.05 | 750.5 | 0.0 | | | EL=53m |
| NO.7 | 10.00 | 0.1 | 4.80 | 48.0 | 0.0 | | | 43.3 | 21.65 | 216.5 | EL=53m |
| NO.7 + 10.00 | 10.00 | 1.0 | 0.55 | 5.5 | | | | 45.4 | 44.35 | 443.5 | EL=53m |
| NO.8 | 10.00 | 4.9 | 2.95 | 29.5 | | | | 80.4 | 62.90 | 629.0 | EL=53m |
| NO.8 + 10.00 | 10.00 | 32.2 | 18.55 | 185.5 | | | | 153.3 | 116.85 | 1,168.5 | EL=52m |
| NO.9 | 10.00 | 27.9 | 30.05 | 300.5 | | | | 34.6 | 93.95 | 939.5 | EL=52m |
| NO.9 + 9.79 | 9.79 | 0.0 | 13.95 | 136.6 | | | | 0.0 | 17.30 | 169.4 | EL=52m |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| 合計 | 153.46 | | | 2,123.7 | m ³ | | 10,040.0 | m ³ | | 3,566.4 | m ³ |

土工数量計算書

令和7年度 穴喰地区地域防災公園 造成工事

| 測点 | 点間距離 | 硬岩 | | | | | | | | | 備考 |
|--------------|--------|------|-------|-------|----|----|----|----|----|----|----------------|
| | | 断面 | 平均 | 数量 | 断面 | 平均 | 数量 | 断面 | 平均 | 数量 | |
| NO.1 +16.30 | | | | | | | | | | | EL=53m |
| NO.2 | 3.67 | | | | | | | | | | EL=53m |
| NO.2 +10.00 | 10.00 | | | | | | | | | | EL=53m |
| NO.3 | 10.00 | | | | | | | | | | EL=53m |
| NO.3 +10.00 | 10.00 | | | | | | | | | | EL=53m |
| NO.4 | 10.00 | | | | | | | | | | EL=53m |
| NO.4 + 10.00 | 10.00 | | | | | | | | | | EL=53m |
| NO.5 | 10.00 | 0.0 | | | | | | | | | EL=53m |
| NO.5 + 10.00 | 10.00 | 22.2 | 11.10 | 111.0 | | | | | | | EL=53m |
| NO.6 | 10.00 | 18.4 | 20.30 | 203.0 | | | | | | | EL=53m |
| NO.6 + 10.00 | 10.00 | 9.5 | 13.95 | 139.5 | | | | | | | EL=53m |
| NO.7 | 10.00 | 0.1 | 4.80 | 48.0 | | | | | | | EL=53m |
| NO.7 + 10.00 | 10.00 | 1.0 | 0.55 | 5.5 | | | | | | | EL=53m |
| NO.8 | 10.00 | 0.0 | 0.50 | 5.0 | | | | | | | EL=53m |
| NO.8 + 10.00 | 10.00 | | | | | | | | | | EL=52m |
| NO.9 | 10.00 | | | | | | | | | | EL=52m |
| NO.9 + 9.79 | 9.79 | | | | | | | | | | EL=52m |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| 合計 | 153.46 | | | 512.0 | | | | | | | m ³ |

全体掘削量 16,242.1 m³
 土砂掘削量 2,123.7 m³
 軟岩掘削量 13,606.4 m³
 軟岩掘削量 512.0 m³